



आईएसओ 9001-2015 पत्तन
AN ISO 9001-2015 PORT

मुरगांव पत्तन प्राधिकरण

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
समुद्री विभाग, प्रशासनिक कार्यालय, हेडलैंड सडा, गोवा - 403804

MORMUGAO PORT AUTHORITY

(Ministry of Ports, Shipping and Waterways, Govt. of India)
Marine Department, Administrative Office, Headland Sada, Goa - 403804
Email: dc@mptgoa.gov.in, Website: www.mptgoa.gov.in



SAGARMALA
PORT LED PROSPERITY

DC/CO/FAS/2023/01199

11.10.2023

To,
All the Parties

Sub: Budgetary Quotation for Comprehensive Annual Maintenance Contract of Fire Alarm System at MPA Signal Station

Mormugao Port authority (MPA) has installed Bosch make Fire Alarm System at Port Signal Station building in the year Dec. 2019. List of the Fire Alarm equipment installed at the said building is enclosed as Annexure-I.

Now, Port has decided to maintain the above Fire alarm system through Comprehensive Annual Maintenance Contract (CAMC) for a period of 5 years.

In this regards, you are kindly requested to give the budgetary quotation for Comprehensive Annual Maintenance Contract for Maintenance of Bosch make Fire Alarm System at Port Signal Station building for a period of 5 years.

Terms and conditions of the contract are enclosed. The contractor may inspect the site to acquaint themselves for the system designed and quote their offer.

Kindly submit your budgetary quotation along with applicable terms and conditions if any, latest by 17.10.2023.

Thanking you,

Yours faithfully,

(कप्तान. मनोज जोशी)

Dy. Conservator

II) FIRE ALARMS SYSTEM installed at A.O Building consist of below listed equipment's:-

Sr no	Description	Technical specification	Qty in nos
1	FIRE ALARM PANEL	Make: Bosch , Model: FPA 1200-C loop with required modules & backup Batteries	1
2	SMOKE DETECTOR	Make: Bosch , Model: FPA -425-OT +MS400	12
3	BASE SOUNDER	Make: Bosch , Model: FNM-420-A-BS-RD	3
4	MANUAL CALL POINT	Make: Bosch , Model: FMC-210 -DM-G- R+FMM-KEY- Form G/H	3

I) TERMS AND CONDITIONS FOR MAINTENANCE OF FIRE ALARM SYSTEM

1.0 PREVENTIVE CHECKUP

The Contractor shall carry out quarterly visits (i.e. after every 3 months once). This consists of measures regarded by Manufacturer as necessary to maintain the equipment in proper operating condition. Preventive checking shall be carried out between Monday to Friday during working hours (9AM to 5PM) planned in advance with Port's representative.

2.0 BREKDOWN MAINTENANCE

This is to be carried out in the event of malfunction, which prevent the operation of the equipment. Work to be carried out during the service coverage time as per the AMC Contract. Breakdown Maintenance includes fault finding, repair or replacement of defective parts and functional checking.

Contractor shall provide emergency minor adjustment CALL-BACK service at no extra charges under the CAMC. This CALL-BACK service shall be extended round the clock on all working days as well as on holiday and is to be attended within 24 hours. The service and breakdown reports to be submitted on the day of service/breakdown or the next day to the Concerned Engineer-in-Charge.

3.0 SPARES AND MATERIALS

The Contractor shall repair or replace any parts of the system which in his opinion are defective at his own cost for ensuring smooth service.

4.0 RESPONSE /TURN AROUND TIME

During the break down of the system at any time, the contractor required to set right/rectify the problem within 24 Hrs of the complaint.

5.0 TOOLS/INSTRUMENTS

The contractor has to provide necessary tools and instruments to their service Engineer for the purpose of servicing the equipment covered by the contract.

6.0 MOCK DRILL AND REPORT:-

As per the guidelines of NCIPL & IB, the quarterly mock drill of all alarm systems provided at need to be carried out and the report shall be submitted to the Concerned Engineer-in-Charge of MPT.

**Comprehensive Annual Maintenance Contract of Fire Alarm System installed at
MPA Signal Station**

Sr. No.	Description	CAMC Year						Total Amount (Rs)
		1 st year CAMC Amount (Rs)	2 nd year CAMC Amount (Rs)	3 rd year CAMC Amount (Rs)	4 th year CAMC Amount (Rs)	5 th year CAMC Amount (Rs)	GST (%)	
1	Comprehensive Annual Maintenance Contract of Fire Alarm System installed at MPA Signal Station							

(Rupees: _____)