



आईएसओ 9001-2015 पल्लन  
AN ISO 9001-2015 PORT

**MORMUGAO PORT AUTHORITY**  
**ENGINEERING (CIVIL) DEPARTMENT.**

**QUOTATION NOTICE**

**QUOTATION NO.CE/Q-15/2023**

**Name of work: “Repairs to Fire fighting Hydrant boxes and replacement of thermostatic and RRL Hose pipes at MPA Hospital at Headland.”**

**DIRECTIONS TO TENDERERS FOR FILLING  
THE SCHEDULE OF QUANTITIES & RATES.**

1. Tenderers are required to fill in their percentage rate at the end of the Schedule of Quantities & Rates, in the space provided for the purpose and unless this is done, their tender will not be considered. Only one percentage rate on all Rates of Schedule of Quantities & Rates shall be named.
2. The Percentage Rate inserted shall hold good for all works under this contract, without reference to quantity or location of the work or the variation in the estimated quantity.
3. Quantity of each item of work mentioned in the Schedule, should be noted and the Percentage rate worked out carefully, having regard to the specifications before submitting the tender, as no variation in rates etc. will be allowed on any ground such as mistake or misunderstanding etc. after the tender has been submitted. The percentage rate, above or below the Schedule/Estimated rate, indicated at the end of the Schedule of Quantities & Rates, will apply to each item, of the tender and any excess in the item that may be directed to be executed by the Chief Engineer.
4. Tenderers are requested to note that though the contract is for item rate, they are required to add or deduct the amount due to this percentage, as the, case may be and work out the final figures(amount of their tenders), at the end of the Schedule of Quantities & Rates.
5. The Percentage Rate should be legibly written in figures as well as in words, in the space provided for Erasures or corrections in figures or in words, without Tenderers initials, will render the tender liable for rejection.

**SUPERINTENDING ENGINEER (HL)**



आईएसओ 9001-2015 पत्तन  
AN ISO 9001-2015 PORT

**MORMUGAO PORT AUTHORITY**  
**ENGINEERING (CIVIL) DEPARTMENT**  
**QUOTATION NO.CE/Q-15/2023**

**Name of work: “Repairs to Fire fighting Hydrant boxes and replacement of thermostatic and RRL Hose pipes at MPA Hospital at Headland.”**

**SCHEDULE OF QUANTITIES AND RATES**

Item No	Description of work	Unit	Qty.	Rate	Total Amount
1	Painting old Hydrant boxes with two coats of approved synthetic enamel paint of Post box Red colour including priming coat of red oxide including preparing the surfaces by scrapping and cleaning. All labour & material complete.	No	21	3000	63000
2	Replacement of hydrant box glass 36"x 18"x3mm. Inclusive of disposal of old damaged glasses within the lead of 500m. at the places directed by Chief Engineer or his representative. All labour & material complete.	No	42	187	7854
3	Replacement of hydrant box rubber gasket for new glass fitting. Inclusive of disposal of old damaged Rubber gasket within the lead of 500m. at the places directed by Chief Engineer or his representative. All labour & material complete.	No	42	150	6300

4	Thermoplast rubber hose pipe ISI mark, 19 mm dia, 30 mtr long, Ball Valve, Hose Nipple, Shutoff Nozzle, jolly clips, Complete Set, inclusive of dismantling of old damaged pipes and disposal of the same within the range of 500 m at the places directed by Chief Engineer or his representative. All labour & material complete.	No	21	1950	40950
5	The hose shall be of Type B. The hose shall be constructed from circular woven jacket having a water proof rubber lining with elastomeric coating. Non-percolating delivery hose, resistance to liquids, chemical, abrasion and heat. Hose shall be of 30mtr long and both side coupling of hose should be brass of 63mm dia. Providing and fixing branded ISI Mark B type RRL Hose with brass binding. Inclusive of dismantling of old damaged Hose pipes and disposal of the same within the range of 500 m at the places directed by Chief Engineer or his representative. All labour & material complete.	No	21	4950	103950
6	Complete servicing of Hydrant points including Greasing/ oiling of locking arrangements, doors, pulleys, handles etc. and ensuring smooth functioning of all items present in Hydrant box. All labour & material complete.	No	21	500	10500
				Total 'A' =	2,32,554.00

**'A' Total amount of quotation inclusive of all taxes (except GST) = "A" = Rs.232554.00**

1. ADD \_\_\_\_\_% (IN FIGURES)

In words \_\_\_\_\_

Over the above amount at "A" i.e Rs. \_\_\_\_\_

OR

2. DEDUCT \_\_\_\_\_% (IN FIGURES)

In words \_\_\_\_\_

From the above amount at "A" i.e. Rs. \_\_\_\_\_

**'B' Total Quoted /Tender Amount inclusive of all Taxes but excluding GST**

In Figure – Rs.

In Words Rupees \_\_\_\_\_

\_\_\_\_\_ Only.

TENDERERS SHOULD SCORE OUT EITHER "ADD" OR "DEDUCT" AS THE CASE MAY BE"

NOTES:

1. Tenderers should score either "ADD "or "DEDUCT" as the case may be.
2. Tenderers are advised in their own interest to inspect the site before tendering.
3. The quantities given above in the schedule of Quantities and Rates are approximate and are furnished for the guidance of the tenderers.

Witness's:

Signature: \_\_\_\_\_

Name: \_\_\_\_\_

Address: \_\_\_\_\_  
\_\_\_\_\_

Tel No: \_\_\_\_\_

Mobile No: \_\_\_\_\_

Date: \_\_\_\_\_

Tenderer's:

Signature: \_\_\_\_\_

Name: \_\_\_\_\_

Address: \_\_\_\_\_  
\_\_\_\_\_

Tel No: \_\_\_\_\_

Mobile No. \_\_\_\_\_