



आईएसओ 9001-2015 पल्लन
AN ISO 9001-2015 PORT

MORMUGAO PORT AUTHORITY
ENGINEERING (CIVIL) DEPARTMENT.

QUOTATION NOTICE

QUOTATION NO. CE/Q- 02/2023

Name of work: “Repairs to roof terrace waterproofing of building having NHAI office and MPA record room at Headland”

**DIRECTIONS TO TENDERERS FOR FILLING
THE SCHEDULE OF QUANTITIES & RATES.**

1. Tenderers are required to fill in their percentage rate at the end of the Schedule of Quantities & Rates, in the space provided for the purpose and unless this is done, their tender will not be considered. Only one percentage rate on all Rates of Schedule of Quantities & Rates shall be named.
2. The Percentage Rate inserted shall hold good for all works under this contract, without reference to quantity or location of the work or the variation in the estimated quantity.
3. Quantity of each item of work mentioned in the Schedule, should be noted and the Percentage rate worked out carefully, having regard to the specifications before submitting the tender, as no variation in rates etc. will be allowed on any ground such as mistake or misunderstanding etc. after the tender has been submitted. The percentage rate, above or below the Schedule/Estimated rate, indicated at the end of the Schedule of Quantities & Rates, will apply to each item, of the tender and any excess in the item that may be directed to be executed by the Chief Engineer.
4. Tenderers are requested to note that though the contract is for item rate, they are required to add or deduct the amount due to this percentage, as the case may be and work out the final figures (amount of their tenders), at the end of the Schedule of Quantities & Rates.
5. The Percentage Rate should be legibly written in figures as well as in words, in the space provided for Erasures or corrections in figures or in words, without Tenderers initials, will render the tender liable for rejection.

SUPERINTENDING ENGINEER (HL)



आईएसओ 9001-2015 पत्तन
AN ISO 9001-2015 PORT

MORMUGAO PORT AUTHORITY
ENGINEERING (CIVIL) DEPARTMENT
QUOTATION NO.CE/Q-02/2023

Name of work: “Repairs to roof terrace waterproofing of building having NHAI office and MPA record room at Headland”

SCHEDULE OF QUANTITIES AND RATES

Sr. No.	Description of work	Approx Qty.	Unit of Qty. in words	Rate in Fig/ words	Amount (Rs)
1.	2.	3.	4.	5.	6.
1	Removing of old laid tar felt waterproofing of slab including stripping old clearing away the same at places pointed out within a lead of 100m, cleaning the surfaces etc. as directed. All labour & material tools & plant etc.complete.	Square Meter	425.00	80.00	34,000.00
2	Repairs to water proofing of the roof slab by placing cement mortar (1:3) 15mm thick using water proofing compound of approved brand, over a base of cement concrete of C.C. (1:2:4) 5 to 8cm (av) thickness including, hacking, removal of old loose IPS layer, cleaning and preparing the surface by applying bonding coat between the layers of approved brand, providing final cementitious slurry mixed with approved water proofing compound. The layers of cement concrete and cement mortar should be laid by giving proper slope towards rainwater pipes placed at the edges towards the parapet walls, and taking up curing, finishing top smooth, thread lining. Works including all tools, scaffolding works etc., and works to be done as per direction of Chief Engineer or his representative. All labour & material etc. complete.	Square Meter	425.00	755.56	3,21,113.00
3	Providing & fixing P.V.C. spout outlet pipes for rain water of 110mm dia (medium) with necessary specials including making joints water tight by using proper sealent & providing & fixing necessary P.V.C. holder bat clamps, removal of old one, cutting & making good the walls etc. All labour & material etc., complete.	Meter	22.50	346.00	7,785.00
	TOTAL	Rs.			3,62,898.00

'A' Total amount of quotation inclusive of all taxes (except GST) = "A" = Rs. 3,62,898.00

1. ADD _____ % (IN FIGURES)

In words _____

Over the above amount at "A" i.e Rs. _____

OR

2. DEDUCT _____ % (IN FIGURES)

In words _____

From the above amount at "A" i.e. Rs. _____

'B' Total Quoted Tender Amount inclusive of all Taxes excluding GST

In Figure – Rs.

In Words Rupees _____ Only.

NOTES:

1. Tenderers should score either "ADD "or "DEDUCT" as the case may be.
2. Tenderers are advised in their own interest to inspect the site before tendering.
3. The quantities given above in the schedule of Quantities and Rates are approximate and are furnished for the guidance of the tenderers.

Witness's:

Signature: _____

Name: _____

Address: _____

Tel No: _____

Mobile No: _____

Date: _____

Tenderer's:

Signature: _____

Name: _____

Address: _____

Tel No: _____

Mobile No. _____

Date: _____