



आईएसओ 9001-2015 पल्लन
AN ISO 9001-2015 PORT

MORMUGAO PORT AUTHORITY
ENGINEERING (CIVIL) DEPARTMENT.

QUOTATION NOTICE

QUOTATION NO. CE/Q-70/2022

Name of work: “Installing prefabricated ladders at Mooring dolphins, Port craft jetty and Breakwater at Harbour”

**DIRECTIONS TO TENDERERS FOR FILLING
THE SCHEDULE OF QUANTITIES & RATES.**

1. Tenderers are required to fill in their percentage rate at the end of the Schedule of Quantities & Rates, in the space provided for the purpose and unless this is done, their tender will not be considered. Only one percentage rate on all Rates of Schedule of Quantities & Rates shall be named.
2. The Percentage Rate inserted shall hold good for all works under this contract, without reference to quantity or location of the work or the variation in the estimated quantity.
3. Quantity of each item of work mentioned in the Schedule, should be noted and the Percentage rate worked out carefully, having regard to the specifications before submitting the tender, as no variation in rates etc. will be allowed on any ground such as mistake or misunderstanding etc. after the tender has been submitted. The percentage rate, above or below the Schedule/Estimated rate, indicated at the end of the Schedule of Quantities & Rates, will apply to each item, of the tender and any excess in the item that may be directed to be executed by the Chief Engineer.
4. Tenderers are requested to note that though the contract is for item rate, they are required to add or deduct the amount due to this percentage, as the, case may be and work out the final figures(amount of their tenders), at the end of the Schedule of Quantities & Rates.
5. The Percentage Rate should be legibly written in figures as well as in words, in the space provided for Erasures or corrections in figures or in words, without Tenderers initials, will render the tender liable for rejection.

EXECUTIVE ENGINEER



आईएसओ 9001-2015 पत्तन
AN ISO 9001-2015 PORT

MORMUGAO PORT AUTHORITY
ENGINEERING (CIVIL) DEPARTMENT

QUOTATION NO.CE/Q-70/2022

Name of work: "Installing prefabricated ladders at Mooring dolphins, Port craft jetty and Breakwater at Harbour"

SCHEDULE OF QUANTITIES AND RATES

Sr. No.	Description of work	Approx Qty.	Unit of Qty. in words	Rate in Fig/ words	Amount (Rs)
1.	2.	3.	4.	5.	6.
1	<p>Fixing pre-fabricated new mild steel ladders (typical as shown in the drawing) including taking the pre-fabricated ladders to the site from MM/MPA workshop and fixing/ welding in position to the Mooring Dolphins as directed, including drilling holes in the fender wall/vertical surface and horizontal deck slab etc., wherever required as directed, providing & fixing MS anchor bolts 25 mm dia and 200mm long (24 nos) embedded 150mm in the concrete including grouting with Lockfix P compound of Fosroc make, including scaffolding, welding machine, cutting machine, welding rods, safety equipments, painting the structural members with two coats of approved anti corrosive paint over a coat of red oxide zinc chromite primer, transporting etc. including dismantling the damaged MS ladders and stacking at designated place at MM/MPA All labour, material, tools & plant etc. complete.</p> <p>Note:(1) fabricated ladders will be supplied free of cost at MM workshop , Baina. (2) Transportation to be arranged by the Contractor for ladders (3)All ancillary work related to fixing of ladder etc. complete (4) No additional payment will be done for other related works)</p>	5.00	Number	22,876.00	1,14,380.00

2	All specifications as per item no 1 above but only fixing the ladder to the existing ladder with necessary splice plates including cutting at suitable locations, welding plates all around without disturbing the anchor locations on the deck slab. All labour, material, tools & plant etc. complete.	4.00	Number	18,413.00	73,652.00
3	Supply of Launch for shifting of material, workmen, staff for execution & inspection for a period of minimum 15 days or till completion of the wok. All expenses chargeable to the Contractor. (LS=1 No)	1.00	Number	2,00,000.00	2,00,000.00

Total (A) Rs.3,88,032.00

'A' Total amount of quotation inclusive of all taxes (except GST) = "A" = Rs. 3,88,032.00

1. ADD _____ % (IN FIGURES)

In words _____

Over the above amount at "A" i.e Rs. _____

OR

2. DEDUCT _____ % (IN FIGURES)

In words _____

From the above amount at "A" i.e. Rs. _____

'B' Total Quoted Tender Amount inclusive of all Taxes excluding GST

In Figure – Rs.

In Words Rupees _____ Only.

NOTES:

1. Tenderers should score either "ADD "or "DEDUCT" as the case may be.
2. Tenderers are advised in their own interest to inspect the site before tendering.
3. The quantities given above in the schedule of Quantities and Rates are approximate and are furnished for the guidance of the tenderers.

Witness's:

Signature: _____

Name: _____

Address: _____

Tel No: _____

Mobile No: _____

Date: _____

Tenderer's:

Signature: _____

Name: _____

Address: _____

Tel No: _____

Mobile No. _____

Date: _____

