

मुर्गांव पत्तन न्यास  
MORMUGAO PORT TRUST  
इंजीनियरी यांत्रिक विभाग  
ENGINEERING MECHANICAL DEPARTMENT  
(इ-तक अनु ाग)  
E-TECH SECTION

TENDER FOR "Supply and Installation of additional 15 nos. CCTV Cameras at Operational Areas"

TENDER NO. CME/XEN(E-Tech)/M-22/2020/02

**ADDENDUM**  
**CORRECTIONS / ADDITIONS / DELETIONS, ETC...**

[Total Number of Pages: 1]


NOTE:

1. Addendum is issued consequent to the queries received for the Pre Bid on 19.11.2020. This "Addendum" should be read in conjunction with Tender Document reference no. **CME/XEN(E-Tech)/M-22/2020/02**
2. Consequential changes, arising out of this Addendum, will be deemed to have been effected, even if the same were not incorporated specifically in the Tender Document.
3. All other terms and conditions of the Tender Document will remain unchanged.
4. One set of this "Addendum", along with one set of Tender Document, shall be submitted along with the Techno-Commercial Offer (in Cover-I), with each page of it, duly signed and stamped, as token of acceptance.

  
CHIEF MECHANICAL ENGINEER (I/C)

**PRE-BID CLARIFICATIONS - Tender No. CME/XEN(E-Tech)/M-22/2020/02  
PRE BID QUERIES OF "Supply and Installation of additional 15 nos. CCTV Cameras at Operational Areas"**

Sr. no.	Reference No in the tender	Pg. No.	Tender Conditions	Bidders Queries	MPT Clarification
1.	2.4.8	25	Cisco/ Brocade 24 port 10/100/1000Mbps and 4 SFP.	Bidder recommended to use enterprise class switches and not SMB class, as SMB class switches would not be able to handle the load.	Tender Conditions prevail.
2.	SECTION V, Sr. No. 21	59	Supply, installation, testing and commissioning of 15Mtr hot dipped Galvanised triangular tower with safety casing and landing, Lightning arrestor and earth pit.	Bidder requested to provide triangular tower design and specifications.	Contractor is required to erect a triangular lattice type structure with columns of 1.5" dia pipe and 12mm bracing rods. The structure has to be mounted on RCC foundation.
3.	SECTION V, Sr. No. 22	59	Supply, installation, testing and commissioning of 6Mtr hot dipped Galvanised 3" Pipe.	Bidder requested to include provision for easy and safe climbing.	Contractor shall inspect the site and make necessary arrangements for safe and easy climbing.  Tender Conditions prevail.
4.	2.1.3.c	21	One PTZ Camera on High- mast belonging to JSW. OFC to be laid from Gate No. 1 to old Church. A 15mtr triangular structure to be erected near the church to mount the wire-less unit to bridge between the church and the camera that will be mounted on the high-mast in JSW premises.	Bidder requested to confirm OFC laying.	Contractor shall lay the optical fiber cable (OFC) on the existing wall from Gate No. 1 to Old Church using saddles.
5.	2.4.11	26	UPS shall deliver 100% power without de-rating Battery, backup provided shall be for minimum one hour.	Bidder enquired if 1 hour back-up is required with full load or only cameras and accessories.	The UPS should have a minimum backup of 15 minutes at 100% load with a built-in battery of not less than 7AH/12V.


  
 20/11/2020  
 20/11/2020  
 20/11/2020