

**MORMUGAO PORT TRUST
ENGINEERING CIVIL DEPARTMENT**

:“ Maintenance painting of 3 Nos (G+1),1 No. (G+3) B Type ,15 No (G+1) C Type and 2 Nos (G+1)D type)at Headland .”.

BOQ

Item no	Description of item	Unit	Qty	Rate	Amount
1	Internal whitewashing and painting over old work type'B' quarters (G+1) walls, ceiling, doors, windows, ventilators, grills etc. as per detail technical specifications and as directed at site by performing following painting job/ items with all labour and materilas and having approzimate quantities as under: a) White washing with lime in two coats approx. area = 217.00sqm. b) Painting of iron/ metal works with synthetic enamel paint in two coats, applying approved primer of Red Oxide Zinc Chromite in one coat. approx. area = 7sqm. c) Painting woodwork with synthetic enamel paint in two coats. approx. area = 45.00Sqm. d) Painting masonry/ concrete plstered surfaces with synthetic enamel paint in two coats. approx. area = 36.00sqm	Lump sum	3	18979.28	56937.84
2	Internal whitewashing and painting over old work type 'B' quarters (G+3) walls, ceiling, doors, windows, ventilators, grills etc. as per detail technical specifications and as directed at site by performing following painting job/ items with all labour and materilas and having approzimate quantities as under: a) White washing with lime in two coats approx. area = 205.00sqm. b) Painting of iron/ metal works with synthetic enamel paint in two coats, applying approved primer of Red Oxide Zinc Chromite in one coat. approx. area = 10sqm. c) Painting woodwork with synthetic enamel paint in two coats. approx. area = 60.00Sqm. d) Painting masonry/ concrete plstered surfaces with synthetic enamel paint in two coats. approx. area = 27.00sqm	Lump sum	1	20323.26	20323.26

3	Internal maintenance painting of C type Qtr (typical) at Headland. All labour & materials tools & plant & surface preparation etc. complete. Note: Detailed items with lumpsum quantities as mentioned below.	Lump sum	15	□ 46,633.18	□ 6,99,497.70
	{Approximate quantities as a) whitewash in two coats= 165.61 sq.m b) painting two coats OBD over a coat of primer=111.67Sq. m c) painting two coats of synthetic enamel paint over primer coat including scrapping=17.09sq.m d) painting woodwork in two coats =78.87 Sq.m, e) painting wood/ wood based surface with two coat of touch wood =19.74 sq.m ,f) Painting old masonry/concrete/plastered surfaces with two coats= 35 sq. m , including surface preparation etc. complete } Lump Sum=1 no				
4	Internal maintenance painting of D type Qtr (typical) at Headland. All labour & materials tools & plant & surface preparation etc. complete. Note: Detailed items with lumpsum quantities as mentioned below.	Lump sum	2	□ 96,149.07	□ 1,92,298.14
	{Approximate quantities as) a) whitewash in two coats= 277.67 sq.m b) painting two coats OBD over a coat of primer=334.26Sq. m c) painting two coats of synthetic enamel paint over primer coat including scrapping=32.46sq.m d) painting woodwork in two coats =85.85 Sq.m, e) painting wood/ wood based surface with two coat of touch wood =62.07 sq.m ,f) Painting old masonry/concrete/plastered surfaces with two coats= 32.79 Sq. m , including surface preparation etc. complete } Lump Sum=1 no				
					□ 9,69,056.94

