

**MORMUGAO PORT TRUST**  
**ENGINEERING MECHANICAL DEPARTMENT**

**NOTICE INVITING BUDGETORY OFFERS**

Name of Work	<b>NAME OF WORK “UNDERGROUND CABLE LAYING IN PORTS RAILWAY YARD”</b>
Date of submission of budgetary quotation	On or Before <b>09/08/2021 at 15:00 Hrs.</b>
Address for communication:	<b>Executive Engineer(E-HL),</b> Mechanical Engineering Department, Mormugao Port Trust, Electrical Section, 1st Floor, Admin. Building, Headland sada Vasco-de-Gama Goa - 403804
Contact Details	Phone : (0832) 2594241, 2594236 Email : <a href="mailto:xene.mgpt@gmail.com">xene.mgpt@gmail.com</a>
Website	<a href="http://www.mptgoa.gov.in">www.mptgoa.gov.in</a>

**CHIEF MECHANICAL ENGINEER**  
**MORMUGAO PORT TRUST**

## **SCOPE OF WORK:**

- 1.1 Laying underground L.T. Aluminum armoured cable in Ports railway yard of size 4 Core 70 sq mm and 3.5 Core 25 sq mm, by excavating trench of depth 60cms, width 40cms. Including supply and laying of Kadappa. After laying, the cable trench should be back filled with soil and route markers to be provided after every 10metres. (The cable will be supplied by the Port at M.M. depot)
- 1.2 Laying underground L.T. Aluminum armoured cable in Ports railway yard of size 4 Core 70 sq mm and 3.5 Core 25 sq mm. by excavating trench for crossing the Rail track. The depth of trench should be 1.5 mtrs from the bottom of the rail sleeper. Pipes to be laid for crossing the rail track and cable should be laid through the pipes and kadappa to supplied and laid above the pipes. After laying, the cable trench should be back filled with soil and route markers to be provided after every 10metres. (The cable and pipes will be supplied by the Port at M.M. depot)
- 1.3 Laying L.T. Aluminum armoured cable in Ports railway yard of size 4 Core 70 sq mm through the underground pipes already provided below the platform near railway track.
- 1.4 Laying L.T. Aluminum armoured cable in Ports railway yard of size 4 Core 70 sq mm through the existing cable trench near the railway platform.
- 1.5 Supply and installation of heat shrinkable joint kit for 4 core 70 sq mm Aluminium armoured cable.
- 1.6 Terminating the Aluminium armoured cable of size 4 Core 70 sq mm and 3.5 Core 25 sq mm. with necessary lugs and glands.

## **Other Terms and Conditions**

1. Budgetary offer shall be valid for 60 days.
2. Entire work should be completed within 45 days from the 7<sup>th</sup> day of receipt of LOA/P.O.

**PRICE SCHEDULE (BILL OF QUANTITIES)**NAME OF WORK: **Underground cable laying at Ports railway yard**

Sr. No.	Description	Unit	Qty	Rate / Unit in (Rs.)		GST in %	Amount (Rs)
				In figure	In words		
1	Laying underground L.T. Aluminum armoured cable in Ports railway yard in trench of depth 60cms, width 40cms. Including supply and laying of Kadappa. After laying, the cable trench should be back filled with soil and route markers to be provided after every 20metres. (The cable will be supplied by the Port at M.M.)						
	a. size 4 Core 70 sq mm	mtr	70				
	b. size 3.5 Core 25 sq mm	mtr	280				
2	Laying underground L.T. Aluminum armoured cable in Ports railway yard by excavating trench for crossing the Rail track. The depth of trench should be 1.5 mtrs from the bottom of the rail sleeper. Pipes to be laid for crossing the rail track and cable should be laid through the pipes and Kadappa are to be supplied and laid above the pipes. After laying, the cable trench should be back filled with soil and route markers to be provided after every 20metres. (The cable and pipes will be supplied by the Port at M.M.)						
	a. Size 4 Core 70 sq mm	mtr	30				
	b. Size3.5 Core 25 sq mm.	mtr	20				
3	Laying L.T. Aluminum armoured cable in Ports railway yard of size 4 Core 70 sq mm through the underground pipes already provided below the platform near railway track	mtrs	25				
4	Laying L.T. Aluminum armoured cable in Ports railway yard of size 4 Core 70 sq mm through the existing cable trench near the railway platform.	mtrs	700				

5	Supply and installation of heat shrinkable joint kit for 4 core 70 sq mm Aluminium armoured cable						
	a) Supply	No	1				
	b) Installation	No	1				
6	Terminating the Aluminium armoured cable of size 4 Core 70 sq mm and 3.5 Core 25 sq mm. with necessary lugs and glands at both ends						
	a) Supply	LS	LS				
	b) Installation	LS	LS				
<b>TOTAL</b>							

(Rupees \_\_\_\_\_ only)

Note: The bidder shall quote the price exclusive of GST. The bidder shall indicate the applicable GST rate on the goods / services in the price bid. GST shall be paid on the quoted price as applicable.