



AN ISO 9001:2015 PORT

**MORMUGAO PORT TRUST
ENGINEERING (CIVIL) DEPARTMENT**

E-Tender No.:CE/ 36 / 2019

Name of Work : Annual Maintenance Contract (AMC) For Various Painting Works of Staff quarters at Headland for the year 2019-20”

Item No	Description of work	Unit of Qty	Qty.	Rate in (Rs)	Total Amount	
					Rs	Ps
				In Figures & words		
1	<p>Internal whitewashing and painting over old work in type 'A' Qtrs as per detail technical specifications and as directed at site by performing following painting job/items with all labour and materials and having approximate quantities as under:</p> <p>a)White washing with lime in two coat . Aprox .area =168sqm</p> <p>b)Painting iron work/metal with synthetic enamel paint in two coats , applying primer of Red Oxide Zinc Chromite in one coats . Aprox. area =5.00sqm</p> <p>c)Painting woodwork with synthetic enamel paint in two coats. Aprox. area =36.00sqm</p> <p>d)Painting Masonry/ concrete plastered surfaces with synthetic enamel paint in two coats . Aprox. area =40.00sqm</p>	Nos	5.00	11468.00	57340.00	
2	<p>Internal whitewashing and painting over old work in type 'B' Qtrs(G+1) as per detail technical specifications and as directed at site by performing following painting job/items with all labour and materials and having approximate quantities as under:</p> <p>a)White washing with lime in two coat .Aprox .area =217sqm</p> <p>b)Painting iron work/metal with synthetic enamel paint in two coats over a coat primer Red Oxide Zinc Chromite in one coat . Aprox area =7.00sqm</p> <p>c)Painting woodwork with synthetic enamel paint in two coats .Aprox area =45.00sqm</p> <p>d)Painting Masonry/ concrete plastered surfaces with synthetic enamel paint in two coats. Aprox area =36.00sqm</p>	Nos	12.00	13222.00	158664.00	
3	<p>Internal whitewashing and painting over old work in type 'B' Qtrs.(G+3) . as per detail technical specifications and as directed at site by performing following painting job/items with all labour and materials .etc having approximate quantities as under:</p> <p>a)White washing with lime in two coat . .Aprox .area =205sqm</p> <p>b)Painting iron work/metal with synthetic enamel paint in two coats over a coat of primer Red Oxide Zinc Chromit. Aprox. .area =10.00sqm</p> <p>c)Painting woodwork with synthetic enamel paint in two coats . Aprox. area =60.00sqm</p> <p>d)Painting Masonry/ concrete plastered surfaces with synthetic enamel paint in two coats. . Aprox.area =27.00sqm</p>	Nos	8.00	14364.00	114912.00	

<p>4</p>	<p>Internal whitewashing,distemping, painting and polishing over old work in type 'C' Qtrs (G+1) as per detail technical specifications and as directed at site by performing following painting job/items with all labour and materials ..etc having aproximate quantities as under:</p> <p>a)White washing with lime in two coat . Aprox .area =166sqm .</p> <p>b) Painting walls ,ceiling ..etc withcement primer in one coat.Aprox. area =112 sqm</p> <p>c)Painting walls , ceiling with Oil bound distemper in two coats overa coat of primer . Aprox.. area =112.00sqm</p> <p>d))Painting iron work/metal with synthetic enamel paint in two coats over a coat of primer Red Oxide Zinc Chromit. Aprox. area= 17.00sqm</p> <p>e)Painting woodwork.with synthetic enamel paint in two coats .Aprox area =79.00sqm</p> <p>f)Painting masonry/ concrete plastered surfaceswith synthetic enamel paint in two coats . Aprox .area =35.00sqm</p> <p>g) painting wood based surface withTouchwood polish in two coats.Aprox. area=20.00 sqm</p>	<p>Nos</p>	<p>10.00</p>	<p>31858.00</p>	<p>318580.00</p>
<p>5</p>	<p>Internal whitewashing,distemping, painting and polishing over old work in type 'D' Qtrs (G+1) as per detail technical specifications and as directed at site by performing following painting job/items with all labour and materials ..etc having aproximate quantities as under:</p> <p>a)White washing with lime in two coat . .Aprox. area =278.00sqm</p> <p>b)Painting walls ,ceiling ..etc with cement primer in one coat .Aprox .area =334.00sqm</p> <p>c)Painting walls , ceiling with Oil bound distemper in two coats over a primer coat . Aprox. area =334.00sqm</p> <p>d)Painting iron work/metal with synthetic enamel paint in two coats over one coat of primer Red Oxide Zinc Chromit. Aprox. area= 32.00sqm</p> <p>e)Painting. woodwork.with synthetic enamel paint in two coats .Aprox. area =86.00sqm</p> <p>f)Painting masonry/ concrete plastered surfaceswith synthetic enamel paint in two coats . Aprox. area =33.00sqm</p> <p>g) painting wood based surface withTouchwood polish in two coats .Aprox. area=62.00 sqm</p>	<p>Nos</p>	<p>3.00</p>	<p>64816.00</p>	<p>194448.00</p>
<p>6</p>	<p>Internal whitewashing,distemping, painting and polishing over old work in HOD bungalow(G +1) . as per detail technical specifications and as directed at site by performing following painting job/items with all labour and materials ..etc having aproximate quantities as under:</p> <p>a)White washing with lime in two coats. Aprox. area =145.00sqm</p> <p>b)Painting walls ,ceiling ..etc with cement primer Aprox. area =569.00sqm</p> <p>c)Painting walls , ceiling with Oil bound distemper in two coats over a coat of primer . Aprox. area =569.00sqm</p>				

d)Painting iron work/metal with synthetic enamel paint in two coats over a coat coat of primer Red Oxide Zinc Chromit. Aprox. area= 61.00sqm				
e)Painting woodwork with synthetic enamel in two coats .Aprox. area =121.00sqm	Nos	2.00	92685.00	185370.00
f)Painting wood based surface withTouchwood polish in two coats .Aprox. area=41.00 sqm				
TOTAL,			Rs.	1029314.00
TOTAL AMOUNT OF TENDER excluding GST = "A"				1029314.00
I hereby agrees to execute the work at			ABOVE/BELOW or AT PAR to the Estimated amount put to tender	
QUOTED AMOUNT				
DIFFERENCE AMOUNT				
" This is a Digitally Signed Document"				