



AN ISO 9001:2015 PORT

**MORMUGAO PORT TRUST**  
**ENGINEERING (CIVIL) DEPARTMENT.**  
**QUOTATION NOTICE**  
**QUOTATION NO. CE/Q- 29(R1) /2019**

Sealed item rate quotations are invited from contractors registered with Engineering (Civil) Department of Mormugao Port Trust for undertaking the work of **“Repairs to the security wall in GCB area.”**

Cost of quotation	: Free of cost
Earnest Money Deposit	: <b>Rs.1,750/-</b>
Estimated cost of work	: <b>Rs. 87061 /-</b>
Time limit of completion	: <b>01(One) Month</b>

The quotation form can be obtained from the office of the Chief Engineer, Mormugao Port Trust, Headland Sada, during office hours from. **22/05 /2019 to 29/05/2019**, on payment of free of cost Volume I comprising of Instruction to Tenderers, General and Special Conditions, General Specifications etc. of Mormugao Port Trust will be considered as part of Quotation Form.

GST registration for the bidder is mandatory. Bidder has to enclose attested copy of the GST Registration along with the quotation. GST has to be claimed extra as applicable while submitting the bill/bills. Tenderer should comply with all regulations of EPF, ESI, ALC, etc. No bill will be forwarded if the above regulations are not followed.

Quotation shall be accompanied by Earnest Money Deposit of **Rs. 1750/-** either deposited with FA&CAO Mormugao Port Trust in Cash or enclosed Demand draft. Quotation without Earnest Money Deposit in the stipulated form will not be considered.

The interested firms may alternatively download the Quotation Document from the Mormugao Port Trust web site <http://www.mptgoa.com>. The downloading of the Tender Documents shall be carried out strictly as provided on website. No editing, addition/deletion of matter shall be permitted. If such action is observed at any stage, such offer is liable for outright rejection.

**A printed set vol-I issued to the contractor contains instructions to the Tenderers, General and Special Conditions of Contract, General specifications forms an integral part of the Tender Documents.**

Quotation duly completed should reach the office of the Chief Engineer, Mormugao Port Trust, Headland Sada by **15.00** hours on **29/05/2019**, and they will be opened at **15.30** hours on the same day in the presence of such quoters as may wish to be present.

The Port Trust reserves the right to reject any or all the quotations without assigning any reasons thereof.

CHIEF ENGINEER

Headland Sada.

Date :-



AN ISO 9001:2015 PORT

**MORMUGAO PORT TRUST**  
**ENGINEERING (CIVIL) DEPARTMENT**

**QUOTATION NO. CE/Q- 29(R1) /2019**

**APPENDIX – I**

Name of work: “Repairs to the security wall in GCB area.”

<b>Particulars</b>		<b>Clause of G.C.</b>	
S.N.	Particulars	Clause of G. C.	Details
1.	Amount of Security Deposit and time	-----	EMD and 10 % retention money recovered from bills
2.	Period for commencement from the Chief Engineer's orders to commence.	-----	3 days
3.	Contract period	-----	<b>01 (One) Month</b>
4.	Amount of liquidated damages.	-----	Calculated at 0.5% value of the contract per week of seven days, or part thereof subject to a ceiling of 5% value of the contract.
5.	Free Period of maintenance.	-----	6 Months
6.	Percentage of retention from each running account bill	-----	10%.of work done For each running bill.
7.	Limit of Retention Money	-----	10% value of the contract.
8.	Total Security Deposit and Retention Money.	-----	EMD Plus 10% value of the contract. Both will be released only after successful completion of maintenance period .
9.	Minimum amount of interim Certificate.	-----	Full & Final bill

10.	Time within which payment to be made after contractor's submission of the bill.	54(1)	100% payment within 5 days of submission of undisputed joint measurement recorded bill and in quadruplicate after obtaining signature of JE/EA and AEN/AXEN concerned (2 copies to Head Office) with all supporting documents.
-----	---	-------	--

---

**SIGNATURE OF THE QUOTER**



AN ISO 9001:2015 PORT

**MORMUGAO PORT TRUST**  
**ENGINEERING (CIVIL) DEPARTMENT**

**QUOTATION NO. CE/Q-29(R1) /2019**

**Name of Work: “Repairs to the security wall in GCB area.”**

**ADDITIONAL SPECIAL INSTRUCTIONS**

1. The work shall be carried without disturbing the operation of Port or other agencies working in the area.
2. All materials bought for use shall be stored properly in a store room, Register of account of materials to be maintained at site.
3. The Plant/machinery/craft and workman shall be insured during the work and receipts of payment made towards premiums shall be submitted to the Chief Engineer.
4. The Plant/machinery required during the maintenance period shall be arranged by the contractor during the maintenance period at his own cost.
5. The Quoter shall also assess and include the cost of materials, labour, tools and plant and machinery/equipment for the maintenance works that may be required to be carried out by him during the free maintenance period.
6. Quoters are advised to go through the Schedule of Quantities and Rates and sequence of work before submission of the tender. They are also advised to inspect the site, ascertain for themselves the nature and the extent of work involved and also obtain all clarifications they may require before filling in the tender.
7. Quoters are required to sign with date the Schedule of quantities and Rates and the form of Quotation and fill in all the particulars and details called for therein. Unsigned quotations, without the details called for are liable for rejection.

## 8. Measurements

The quantities provided for in the Schedule of Quantities and Rates are only approximate and are given to provide a common basis for tendering. The actual quantity may differ from those provided for in the Schedule in view of the complexity of the work. Payments will be made according to the actual quantities of work ordered and carried out, jointly measured by the representative of Chief Engineer and the contractor.

## 9. Rates and Prices to be inclusive.

The rates entered in the Schedule of Quantities by the contractor shall include the provision of all supporting special equipment, labour of required skill, supervision, materials, erection, overheads and profits, watch and ward, insurance charges, during execution and every incidental and contingent costs and charges, whatsoever, inclusive of all taxes, GST will be paid as Extra as applicable etc. if any, for compliance with conditions of contract and specification.

10. The specifications are intended to cover the execution of all works, necessary to complete the works, with all materials of accepted standards, as specified in the contract.

## 11. Method of Measurement

### General

Unless stated or billed otherwise, all quantities shall be `net` as they finished and provided in the work. The rates and prices shall include all allowances towards wastage of materials required for use in the work.

12. The quoters will be deemed to have ascertained themselves to the extent and nature of the works involved, the various constraints and high degree of skill involved in the works.
13. Time is the essence of contract and the entire work should be completed in **01 (One) month** as specified in the schedule. The Quoter shall also submit detailed programme for the timely completion of work giving details of gangs/labour/material supply/plant and machinery etc. taking into account the limited time schedule provided.
14. The Contractor`s supervisory staff shall be fully experienced in the type of work to be carried out under their supervision.

15. The contractor shall insure all tools and accessories to workers employed by him during execution of work and submit necessary insurance policies to the Department.
16. It shall be specifically noted that the contractor is expected to mobilise the required equipments and work force required to complete the entire work included in the contract well within the stipulated period.
17. As a statutory requirement, the contractor shall take all measures of safety against fire hazard and electrocution at site as follows:-
  - a) All temporary electric supply connections will be carried out with correct sizes of wires/cables and fuses and other safety devices as required under Electricity Rules in consultation with us.
  - b) One bucket full of water and sand shall be kept at the work spot. A Portable fire extinguisher shall also be kept at the work spot.
18. Quotations with conditions will be out rightly rejected.
19. The Quoter shall inspect the site and fully study the work involved vis-à-vis the quantity and specifications etc. before quoting for the work.
20. Any damage to the property of Port should be made good or compensated by the contractor.
21. After completion of days work/contract period the contractor shall clean, Clear the work site to the satisfaction of the Chief Engineer or his site Representative.
22. Permission for working beyond the normal working hours of the Port or on Sundays and Public Holidays as stipulated under clause No. 42 of General Conditions of Contract, (in the printed booklet) in volume-I of the Tender document will be given to the contractor subject to his agreeing to bear the cost of overtime, if any, which may have to be paid to the Port's Supervisory staff.
23. The contractor and his workers /agents shall be required to obtain from MPT and display a Photo Identity Card during entry, stay and exit from the Port Security areas guarded by CISF personnel`
24. All applications for issuance of Photo Identity Card shall be routed through The Chief Engineer, who shall forward the same to the Port's Traffic Department, whose pass section will issue the Photo Identity Card to the Contractor or his agent at free of cost and the same shall be valid for the Duration of the contract..

25. Hot work permit will have to be obtained whenever required as directed.

26. GST registration for the bidder is mandatory. Bidder has to Enclose attested copy of **GST** Registration No along with the Tender. **GST** has to be claimed extra as applicable while Submitting the Bill/bills.

**27. “The bidder shall quote the price exclusive of GST. Applicable GST shall be paid on the quoted price. The bidder shall indicate the applicable GST rate on goods/Services in the price bid”**

28. **a. Security Deposit:** EMD deposited along with the tender will be Converted as Security deposit

**b. Retention money:** Retention money shall be deducted from each Running account bill at 10 % of gross value of work done to the Limits of 10 % of contract value.

**c. Refund of Security deposit and Retention money:** S.D and Retention money shall be refunded only after successful Completion of Defect liabilities period (Free Maintenance period) if Applicable.

29. Unregistered Venders under **GST** has to submit Declaration that GST is not applicable to them, due to turnover of their firm being less than 20 Lakhs.

**30. Scope of work :**

1. Providing coping of cement concrete (1:2:4) mix using 20mm black trap stone metal.
2. Plastering/finishing with C.M. (1:3) 10mm thick (avg.) in single coat.
3. Providing and fixing barbed wire fencing in 10 rows to M.S. angles.
4. Supplying & Providing approved (as per existing ) concertina wire coil fencing.
5. Supplying & erecting in position structural steel work in single section.
6. Repairs to the chainlink fencing over security wall from ROB to Rumdeshwar temple by fixing the existing chainlink fencing back in position.

**Chief Engineer**





AN ISO 9001:2015 PORT

**MORMUGAO PORT TRUST**  
**ENGINEERING (CIVIL) DEPARTMENT**

**QUOTATION NO. CE/Q- 29(R1)/2019**

Name of Work: **“Repairs to the security wall in GCB area.”**

**SCHEDULE OF QUANTITIES AND RATES**

Sr. No.	Description of work	Approx. Qty.	Unit of Qty. in words	Rate in Fig/ words	Amount Rs. Ps.
1.	2.	3.	4.	5. 6.	7.
1	Providing coping of cement concrete (1:2:4) mix using 20mm black trap stone metal out of quarried boulders as coarse aggregate including mixing, depositing, side shuttering, consolidating, levelling, curing etc. All labour and material etc. complete.	4.00	Cubic Metre		
2	Plastering/finishing with C.M. (1:3) 10mm thick (avg.) in single coat including raking out joints, hacking, cleaning and preparing the surface, curing, chamfers, beading, scaffolding, all leads, lifts making all bands, bays, fluting etc. All labour & material etc. complete.	30.00	Square Metre		
3	Providing and fixing barbed wire fencing in 10 rows to M.S. angles including welding of M.S. rods of 6mm dia. , to the M.S. angles, hire of welding set/cutting set etc. All tools & plant , labour and material etc. complete.	25.00	Metre		

4	Supplying & Providing approved (as per existing ) concertina wire coil fencing of 610mm diameter with 26/27 swg barbed concertina strips of 19mm width and turn circles of 80 nos. coil in 8 to 9 metres length etc. All tools, plant, labour & material etc. complete	25.00	Metre		
5	Supplying & erecting in position structural steel work in single section (light sections less than 34 kg./m) including Cutting, hoisting, fixing in position and cleaning the surface, painting two coats of approved quality synthetic enamel paint of approved colour/ shade over a coat of red oxide zinc chromite primer etc. All labour & materials tools & plant etc. complete.	1.00	Quintal		
6	Repairs to the chainlink fencing over security wall from ROB to Rumdheshwar temple by fixing the existing chainlink fencing back in position by using G.I wire including providing additional old chainlink fencing/M.S.,Tor steel rods/ wherever required available at AXEN/GCB section including transporting to site including straightening the existing M.S. angles wherever required provided over the security wall, dismantling of concrete wherever required including erecting the existing M.S. angles back in position by providing concrete as per item no.1 , etc. All tools, plant labour and material etc. complete.(Approx length of security wall from ROB to Rumdheshwar temple is 800Metres). <b>Note:</b> Concrete provided for grouting of angles will be paid under item No. 1.	1.00	L.S.		

Total amount in figures Rs. \_\_\_\_\_

Total amount in words (Rupees \_\_\_\_\_ only)

including all taxes but excluding GST

It is certified that I / we have written the unit rates in figures and words.

Name & Address of Quoter

\_\_\_\_\_  
\_\_\_\_\_

SIGNATURE OF THE QUOTER

**Date:** \_\_\_\_\_

**Place:** \_\_\_\_\_