MORMUGAO PORT TRUST ENGINEERING MECHANICAL DEPARTMENT

Quotation no. CME/ PD/VIII /2017



QUOTATION

FOR

Repairs, Sand/Grid Blasting, Cleaning and Painting of Catwalk at Berth no.8

Due at 15.30 Hrs. on 02.05.2017

Website: www.mptgoa.com

MORMUGAO PORT TRUST ENGINEERING MECHANICAL DEPARTMENT

Quotations are invited in a sealed cover from authorized firms duly superscribed as **Quotation for** "Repairs, Sand/Grid Blasting, Cleaning and Painting of Catwalk at Berth no.8"

Details about Quotation:

| Quotation invited by | CHIEF MECHANICAL ENGINEER, MORMUGAO PORT TRUST |
|--|--|
| Quotation No. | CME/ PD/VIII /2017 |
| Name of Work | Repairs, sand/grid blasting, Cleaning and Painting of Catwalk at Berth no.8 |
| Security Deposit | 5% of PO value will be retained from the final bill. |
| Completion Period | The work should be completed within 30 days from the date of receipt of the LOI/PO. |
| Liquidated Damages | For delay in supply/work Liquidated Damages, equivalent to 1% of the total contract value/per week or part thereof subject to maximum 5% are liable to be deducted from any moneys due or become due to the Contractor |
| Payment terms | 100% payment will be made within 30 days after satisfactory completion of work on producing invoice complete in all respect. The contractor shall furnish their bank account number PAN card, MICR number Name of the Branch along with Bill for arranging payment made through E.C.S. by the Trust. |
| Bid Validity | 30 Days from the date of opening of the quotation. |
| Guarantee Period | 1 Year from the date of commissioning. |
| Date of submission of bids | 02.05.2017 till15:00 Hrs. |
| Date of Opening of bids | 02.05.2017 at 15:30 Hrs. |
| Address for communication and submission of bid: | Executive Engineer (P&D) 2 nd floor A.O. Bldg, Headland Sada, Engineering Mechanical Dept., Mormugao Port Trust, 403804. |
| Contact Details | Phone :0832-2594218; Email : xenpnd.mgpt@gmail.com |
| Website | www.mptgoa.com |

CHIEF MECHANICAL ENGINEER MORMUGAO PORT TRUST

1. SCOPE OF WORK

Mormugao Port Trust proposes to repair the cat walk structure at Berth no.8 by replacing the badly corroded M.S. members and sand blasting and painting the entire structure.

1.1 TECHNICAL SPECIFICATION

- a) The work shall be carried out as per the price schedule attached with the quotation and in consultation with the Mechanical Department of MPT.
- b) Replacement of badly corroded M.S. members such as angles and plates as per price schedule and as per the size of the existing member at site.
- c) Sand/grid Blasting, cleaning the entire structure to make it rust free and paint the entire structure with two coats of zinc rich epoxy primer and two coats of epoxy finish coats.
- d) Thickness of each coat of primer should be 80 100 microns and that of finish coat should be 45 60 microns.
- e) Storage arrangements for all materials and tools and plants shall be made by the contractor at his own cost.
- f) The old dismantled material shall be Port's property and the same shall be transported and unloaded at M.M. Depot, Baina by the contractor at his own cost. In case of failure of shifting of materials from site immediately after completion of work, the same will be carried out by engaging departmental labour or some other agency at the risk & cost of the contractor.
- g) Contractor shall provide all necessary tools, scaffolding, plants, protective equipments including life jackets etc to its workers, take safety measures as required and follow all safety procedures.
- h) Contractor shall not carry out welding and gas cutting work when the POL carrying ship is at Berth No. 8. Necessary clearance will be given by Port in advance.
- i) Quantities shown in Price schedule are approximate which may vary, depending upon the site condition. Payment will be made as per the site measurement and after due approval of variation statement.
- j) All materials to be used in the structure shall be conforming to relevant ISI specifications or as specified in the quotation and only approved materials/approved brand of materials shall be used.
- k) All the material such as steel, paint, welding electrodes, gas cylinders etc. shall be supplied by the contractor.
- Makes of the material: i) Welding electrodes: L&T, Advani, Orlicon, etc.

ii)Steel: Vizac, TATA, Jindal, SAIL etc.

iii)Paints: Jotun, International, Johnson, Berger etc.

Note: The tenderer shall quote strictly as per 'schedule A1'.

PRICE SCHEDULE

Name of the work: Repairs, Chipping/Sand Blasting and Painting of Catwalk at Berth no.8

| Sr. | Description | Unit | Qty | Unit Rate in (Rs.) | | Amount in (Rs.) |
|-------|--|----------------|------|--------------------|----------|-----------------|
| 110 | | | | In fig. | In words | |
| 1 | Replacement of badly corroded M.S. members such as angles 75x75x10, plates 10mm thick, chequered plate 6mm thick etc. as identified by Port. | Kg. | 3000 | | | |
| 2 | Sand/Grid blasting, cleaning the entire structure to make it rust free to the complete satisfaction of the Port and paint the entire structure with two coats of zinc rich epoxy primer and two coats of epoxy finish coats as per the technical specifications. | M ² | 450 | | | |
| Total | | | | | | |

Office Seal of firm

Note: The offered rates shall be inclusive of all taxes and duties. Service Tax shall be paid extra as applicable.