MORMUGAO PORT TRUST ENGINEERING CIVIL DEPARTMENT

QUOTATION NO. - CE/Q -18 /2019

Name of Work :Repairs to washrooms at GH3 Block of MPT Guest House at Headland.

SCHEDULE OF QUANTITIES AND RATES

Item	Description of Work	Unit	Approx.	Rate in Rs.	Amount
No.		of	Qty.	Fig/Words	Rs Ps.
		Qty			
1	Stripping old cement plastering and clearing away the same at places pointed out within a lead of 100m, cleaning the surfaces etc. As directed. All labour & material tools & plant complete.				
	·	M2	55.00	63.00	3,465.00
2	Plastering with cement mortar (1:3) 10mm thick in single coat for brick walls. All labour & material etc. complete.				
		M2	55.00	275.00	15,125.00
3	Providing skirting/dadooing to the required height with best quality ceramic tiles spartek or equivalent quality set over a base of cement mortar (1:3) 10mm thick including cutting the tiles where required necessary specials, pointing, curing etc. All tools, plant, labour & material complete.				
		M2	70.00	1587.00	1,11,090.00

Total 1,29,680.00

TOTAL AMOUNT OF QUOTATION (Excluding GST) = A = Rs.1,29,680.00

A. 1. ADD	% (IN FIGURES)				
	nt at "A" i.e Rs				
	OR				
2. DEDUCT	% (IN FIGURES)				
From the above amou	ınt at "A" i.e. Rs.				
B.Total Quoted Tende in Figure –Rs.	r Amount inclusive of all Taxes(excluding service tax)				
In Words					
TENDEDEDE CHOULD	SCORE OUT EITHER "ADD" OR "DEDUCT" AS THE CASE MAY BE"				
TENDEKERS SHOULD S	SCORE OUT EITHER ADD OR DEDUCT AS THE CASE MAY BE				
NOTES:					
 Tenderers should may be. 	Tenderers should score either "ADD "or "DEDUCT" as the case				
•	vised in their own interest to inspect the site before				
•	en above in the schedule of Quantities and Rates				
	d are furnished for the guidance of the tenderers.				
Witness's:	Tenderer's:				
Signature	Signature				
Name :					
Nume .	Name :				
Address:	Address:				