

MORMUGAO PORT AUTHORITY
ENGINEERING MECHANICAL DEPARTMENT
ELECTRICAL HARBOUR SECTION

NOTICE INVITING BUDGETORY OFFERS

Name of Work	“Replacement of 05 nos., corroded MS sheet enclosures of Control Panels of the Fire Fighting System with new FRP sheet enclosures at Berth No.8”
Date of submission of budgetary quotation	On or Before 08/08/2022 at 15:00 Hrs.
Address for communication:	Executive Engineer (E-HR), 2nd floor, Mechanical Engineering Department, Mormugao Port Authority, Admin. Building, Headland sada Vasco-de-Gama Goa - 403804
Contact Details	Phone : (0832) 2594207, 2594577 Email : mohamed.shaik@mptgoa.gov.in
Website	www.mptgoa.gov.in

EXECUTIVE ENGINEER (E-HR)
MORMUGAO PORT AUTHORITY

MORMUGAO PORT AUTHORITY
ENGINEERING MECHANICAL DEPARTMENT
ELECTRICAL HARBOUR SECTION

Sub: Replacement of 05 nos., corroded MS sheet enclosures of Control Panels of the Fire Fighting System with new FRP sheet enclosures at Berth No.8

Ref: Budgetary Quotation No. CME/XEN (E)/HR/ H-16/22/B2

Mormugao Port Authority, intends to carryout work of replacement of 05 nos., corroded MS sheet enclosures of Control Panels of the Fire Fighting System with new FRP sheet enclosures at Berth No.8

As such it is requested to kindly furnish budgetary quotation for the same (Scope of work, technical specifications are enclosed at Annexure-I and Price Schedule enclosed at Annexure- II.)

Your budgetary quotation should reach to this office on or before 08/08/2022 at 15:00 Hrs.

Thanking you,

Yours sincerely,

EXECUTIVE ENGINEER (E-HR)

Annexure-I

TECHNICAL SPECIFICATION

1) Scope of work :

- i. The existing MS sheet enclosures of control panel of firefighting system has to be dismantle without disconnecting/damaging the existing connected control cables and electronic/electrical components inside the panel.
- ii. Fabrication and Supply of 5nos., FRP enclosures by providing proper door openings, with locking arrangement and gland plates at the bottom with suitable openings for existing cables as per the dimension given in BOQ. These FRP panels has to be fixed on the existing M.S. frame with nut bolts/washers etc.

2.0 INSTALLATION AND COMMISSIONING

- i. The Contractor shall commence and complete the work as per the BOQ and proper care should be taken. The work is to be carried out as per the site conditions and relevant IS standards.
- ii. The Contractor shall complete the work to the satisfaction of the Chief Mechanical Engineer or his representative.
- iii. The work should be carried out with utmost safety precaution with minimum possible disruption of power supply. The contractor has to ensure that the power supply to the control panels of firefighting system is switched "OFF" during execution of work.
- iv. In case of any welding work at site, the necessary hot work permission has to be obtained from the required section by the contractor.

3.0 OTHER TERMS AND CONDITIONS

- i. The firm is advised to visit the site and get acquainted regarding the nature of the work involved at site conditions before quoting the offer.
- ii. The firm should engage skilled service personnel with the relevant required tools and instruments for supply and execution of the work.
- iii. The Contractor personnel engaged in the work shall follow all safety, security and General Rules enforced by Mormugao Port Authority (MPA) and the firm will only be responsible for the same.
- iv. MPA will not be responsible for any loss or damage of the men / materials / tools / plants engaged by the firm during the work at site / transportation.
- v. The contractor shall shift the left over material after completion of the work as directed by Engineer-in -charge.
- vi. No advance payment will be made.
- vii. Final payment will be made only after handing over the entire system in good working condition.
- viii. Necessary entry passes shall be obtained by the firm at their own cost with the approval of Port Officials.
- ix. Necessary electrical power supply required for installation of enclosures will be provided by MPA at free of cost at nearest possible point. However, the firm should make his own arrangements to take power supply from the nearest source of supply.

MORMUGAO PORT AUTHORITY
ENGINEERING MECHANICAL DEPARTMENT
ELECTRICAL HARBOUR SECTION

ANNEXURE-II

BUDGETORY QUOTATION

NAME OF WORK: Supply and installation of FRP Outdoor Panel Enclosure.

Kindly furnish budgetary offers (exclusive of GST) for the following work:-

Sr. No.	Description of work	Qty.	Unit	Rate Per Unit (Rs)	Amount (Rs)
1	Supply and installation of FRP enclosure with door opening, with gland plate at the bottom with suitable openings for the existing cables and fixing it to the existing M.S. frame with nut bolts, Fire resistant, outdoor type, 2mm thick size 1.2m (length) x 0.8m(Height) x 0.5m (Width).	4	no.		
2	Supply and installation of FRP enclosure with opening door with gland plate at the bottom and fixing it to the existing M.S. frame with nut bolts, Fire resistant, outdoor type, 2mm thick size 0.7m(Length) x 0.5m(height) x 0.5 m(Width)	1	no.		
TOTAL (Rs)					

(In Words Rupees _____ only exclusive of GST)

Note: 1) The rates quoted shall be inclusive of transportation, lodging and boarding, but exclusive of GST. Applicable GST shall be paid extra as applicable.