

MORMUGAO PORT TRUST
ENGINEERING MECHANICAL DEPARTMENT
NOTICE INVITING BUDGETORY OFFERS

Name of Work	NAME OF WORK " <u>Making straight through cable joints & rerouting S&T bldg supply cable</u> "
Date of submission of budgetary quotation	On or Before 14/06/2021 at 15:00 Hrs.
Address for communication:	Executive Engineer(E-HL), Mechanical Engineering Department, Mormugao Port Trust, Electrical Section, 1st Floor, Admin. Building, Headland sada Vasco-de-Gama Goa - 403804
Contact Details	Phone : (0832) 2594241, 2594236 Email : xene.mgpt@gmail.com
Website	www.mptgoa.gov.in

CHIEF MECHANICAL ENGINEER
MORMUGAO PORT TRUST

1. SCOPE OF WORK

- 1.1 Opening the cable fault area by excavating concrete at the fault location/ zone. Supply and making of 2 nos heat shrinkable straight through joints on 1.1 kv grade, Al armoured XLPE cable of size 3.5C x 70 mm².
- 1.2 Removing the concrete up to depth of 30 cms to reroute the cable alongside the excavated concrete portion.
- 1.3 All the excavated area to be made good with concrete as earlier.
- 1.4 The entire work shall be completed within 10 **days** from the receipt of LOA/Purchase order whichever is earlier.

Bill of quantities (BOQ)

Sr. No.	Description	Unit	Qty	Unit Rate in (Rs.)		Amount in (Rs.)	SAC /HS n code	Applicable GST %
				In fig.	In words			
1	Excavation to remove earth/ concrete to expose the cable fault.	Run ning Mtr	10					
2	Supply and making heat shrinkable straight through joint on 1.1 Kv grade 3.5C x 70sq mm L.T. aluminum armoured cable.							
	a) Supply	No	02					
	b) Installation	No	02					
3	Excavation of the concrete surface up to depth of 30 cms to reroute the above cable and restoring the surface as before	Run ning Mtr	10					
Total								

(In Words Rupees _____
_____ only)

Note:

- 1) The quantities mentioned in the BOQ (Bill of Quantities) are indicative but not exhaustive. The payment shall be made at actual.
- 2) The offered rates shall be exclusive of GST.

Date:

Signature:

Place:

Name:

Address:

Office Seal of firm